Additional studies are needed to determine whether or not non-weather sensitive EUI's are actually as different as it appears or if the uncertainties in the estimates from various studies are so large as to cause the differences. Uncertainties arise from such factors as incorrect input data obtained from mail surveys, incorrect formulations of regression equations, and the statistical nature of the conditional demand approach. An alternative explanation is that the differences in non-weather sensitive EUI estimates are due to such causes as varying appliance efficiencies in different samples of buildings, different usage patterns for appliances, and different definitions of floor space and business types. Enduse metering will help to answer these questions, but the small number of buildings sampled and uncertainties in measurements will necessitate careful analysis of such estimates when made available.

There are a number of reasons why differences in estimated EUI's are expected among studies. Several have been mentioned already, these are differences in climate (which impacts heating and cooling), differences in average efficiencies of end-use equipment, and differences in the thermal integrity of the building stock. PG&E is now conducting detailed on-site energy audits of a large number of commercial buildings. It will be interesting to use data collected from these audits to develop EUI's and then compare those EUI's to the ones obtained in the study described here. In conclusion, although the EUI's obtained in our study are generally reasonable in magnitude there is still need to conduct further comparisons to results from other studies. These can be end-use metering studies or other conditional demand studies using on-site data.

Acknowledgements—The authors wish to thank F. Gordon of Bonneville Power Administration for a very thoughtful and helpful review. Additionally, we appreciated the support and interesting discussions with D. Bonney, S. Buller and G. Irwin of Pacific Gas and Electric Company. D. DeBoer helped prepare the typescript and B. Jones performed many of the computer runs.

REFERENCES

- S. Buller, 1982 Commercial Energy Use Survey, Pacific Gas and Electric Company, San Francisco, Calif. (May 1985).
- Combining Engineering and Statistical Approaches to Estimate End-Use Load Shapes, EPRI EA-4310, EPRI, Palo Alto, Calif. (October 1985).
- 3. M. Parti, A. Sebald, and K. Parris, Energy Use and Conservation in the Commercial Sector: A Conditional Demand Study, EPRI Project 2152, EPRI, Palo Alto, Calif. (January 1985).
- P. Ignelzi and K. Train, Economic Estimation of Energy Utilization Indices and Persistance of Savings, Cambridge Systematics, Berkeley, Calif. (November 1984).
- Conversation with Richard Mazzucchi, Battelle Pacific Northwest Laboratories, Richland, WA 99352 (November 1986).
- Colleen Cleary and Barbara Crimmin, Commercial Hourly End-Use Study: Status Report 1982-85, Seattle City Light, Seattle, Wash. (August 1986).
- G. McCollister, B. Hesterberg, I. Turiel, P. Craig, M. Levine, M. Robinson, and J. McMahon, Energy Utilization Intensities for Major End-Uses in the Commercial Sector, Report to PG&E, QED Research Inc., Palo Alto, Calif. (September 1985).
- M. Fels, The Princeton Scorekeeping Method: An Introduction, PU/CEES Report No. 163, Princeton University, Princeton, N.J. (March 1984).
- 9. The weighting factor = P_{ij}/r_{ij} *ft² where i = sampling business type, j = sampling class, which divides customers into five categories according to type of gas and electric account, P_{ij} = number of commercial customers of business type i in sampling class j, r_{ij} = number of respondents of business type i in sampling class j, and ft² is the number of square feet comprising the respondent's premise.
- D. Schultz, End-Use Consumption Patterns and Energy Conservation Savings in Commercial Buildings, presented at ACEEE 1984 Summer Study on Energy Efficiency in Buildings, ACEEE, 1001 Connecticut Ave., Washington, D.C. (August 1984).
- Pacific Northwest Commercial Building Energy Characteristics and Analysis, Synergic Resources Corporation, SRC Report # 7105-R2, Seattle, Wash. (1983).
- 12. Final Report on the Development of an Energy End-Use Data Base for the Commercial Sector Serviced by the Retail Subsidiaries of the New England Electric System in Rhode Island and Massachusetts, Xenergy, Inc. Boston, Mass. (September (1981).

THE KANSAS CITY WARM ROOM PROJECT: ECONOMICS, ENERGY SAVINGS AND HEALTH AND COMFORT IMPACTS

BARBARA SHOHL WAGNER and RICHARD C. DIAMOND

Applied Science Division, Lawrence Berkeley Laboratory, Berkeley, CA 94720, U.S.A.

(Received 8 August 1986)

Abstract—The warm room retrofit is a response to a common problem: how to stay warm in a large, poorly insulated house during the coldest parts of winter. The problem is especially acute for low-income and elderly homeowners who may not have sufficient resources to improve the thermal integrity of their entire house. Although still an experimental technique, the warm room retrofit has the potential for achieving significant energy savings in houses at costs similar to those currently allocated by low-income weatherization programs. The retrofit is a combination of zoning, heating systems modification and insulation which allows the occupant to heat selected areas of her home while maintaining the unused areas at a cooler temperature. This study presents the results from a retrofit project in Kansas City, sponsored by the Urban Consortium in 1985-1986. Nine houses were selected for the study, four controls and five houses that received the warm room retrofit. The houses are all single-family detached structures, occupied by low-income owners (with the owners' ages between 60 and 80 yr), and heated with gas-fired forced-air or gravity-fed furnaces. The warm zone was designed to include the kitchen, bathroom, and one to two additional rooms depending on family size. The costs of the retrofit averages \$1425 per house. Our analysis included regressions of total gas use vs outdoor temperatures to measure savings, which averaged 26%. Because of potential health and safety problems, we also measured indoor air quality before and after the retrofit, sampling levels of indoor radon, nitrogen dioxide, and formaldehyde. An important part of the study was to determine occupant response and the acceptability of the retrofit. The residents participated in the design of the retrofits, and were interviewed after the retrofits were installed to determine improvements in comfort and their satisfaction with the results.

1. INTRODUCTION

Despite some recent easing in energy prices, the need for cost-effective weatherization measures remains acute, particularly for low-income and elderly homeowners. In response, some government agencies and utilities are experimenting with new retrofit strategies, including the warm room retrofit. The warm room retrofit is a modification of a familiar strategy of zoning the house into warm and cool zones, which is achieved in centrally-heated homes through the use of such measures as furnace rebalancing, portable thermostats, special heat-restricting covers for the heat-distribution system, curtains or partitions to enhance zoning, portable heaters, and selected insulation of ducts and exterior walls.

The attraction of warm rooms is the prospect of significant energy savings (theoretically double or triple that of conventional weatherization) at costs equal or below current levels. But a number of questions require answers before widespread installations of warm rooms. The first is whether theoretical savings can actually be achieved: whether the zoning is effective, whether a central heating system remains sufficiently efficient in its new operating mode, and whether the projected costs are realistic. Second, there are questions about health and building safety: whether indoor air quality problems arise or intensify with the zoning, how to prevent moisture damage in the cool areas of the house, and how to avoid water pipe freezing. Third, there are a set of social questions: whether the zoning is acceptable to occupants, or a particular set of occupants; how to insure sufficient flexibility and control over the operation of the house; what measures contribute most to occupant comfort; how the retrofit affects property value; how best to teach occupants to manage their warm rooms.

Pioneering groups in warm room research include the Tennessee Valley Authority, the Institute for Human Development (IHD) in Philadelphia, and Union Electric in St Louis. These groups have explored several different warm room approaches and gained considerable insights into the practical applications of the retrofit and occupant acceptance. To

date, however, there have been few reported results of measured energy savings and no information on the effect of the retrofit on indoor air quality (references describe work of IHD and Union Electric; no published reports are available from TVA).²⁻⁴ Consequently. the object of this study was to measure the energy savings, the air quality, and the occupant response to warm room retrofits in a small group of carefully monitored houses. The project was sponsored by the Urban Consortium and the Department of Energy, and carried out by the city of Kansas City, Missouri, with technical assistance provided by Lawrence Berkeley Laboratory.

2. PROJECT DESIGN

2.1 Selection of houses

Our two objectives in selecting houses were to find houses where a warm room retrofit would be both practical and useful, and where an unambiguous evaluation of energy savings would be possible. Applications for participation in the program were distributed by neighborhood block groups in low-income areas throughout the city. The applications included questions about the appropriateness of the household for the retrofit (rough size of house, number of occupants, interest in project, type of heating system) and questions about fuel use patterns that could affect accurate measurements of savings (willingness to allow a submeter, ability to make weekly readings and to make past billing data available; number of years spent in present house; planned change in number of occupants; use of fireplaces or other auxiliary heaters).

For each of the 44 houses that responded we did a regression analysis of gas consumption vs variable-base degree days and calculated the normalized annual consumption (NAC) for the past two years in order to screen out those houses with weather-normalized fuel use too irregular to allow a clean measurement of warm room energy savings.⁵ We also checked the electricity-consumption data to verify absence of significant electric heating.

Results of the questionnaire and regression analysis were used to screen the original 44 applicants down to a group of 19. At that point, we held a workshop to describe the warm room approach in more detail to the remaining homeowners, and did an on-site audit and interview at each of the 19 houses. In the final selection, we chose 5 houses to receive warm rooms and 9 to serve as control and back-up houses. The process was complete in early 1983, but administrative delays prevented the beginning of actual retrofit work until the fall of 1985. During that time, one of the owners of a house scheduled for retrofit left the program due largely to difficulties making required data readings, as did two of the control houses. One other control house dropped out due to illness and another control stopped sending data in early 1986. One of the control houses was chosen to replace the retrofit house that was dropped. The remaining retrofit and control houses were reliable in sending weekly gas and temperature data, as described below. The following discussion refers to the final group of 5 retrofit and 4 control houses.

2.2 Description of houses

Table 1 summarizes some characteristics of the warm room and control houses. In general, the houses are of moderate size, 1000–1700 ft², except one control with 3600 ft², so that a warm room seemed most practical for small households (1-2 people) whose routines would allow use of a 2-3 room zoned portion of the house during cold weather. While the house size seems modest, we found that larger houses were already strictly zoned, or housed too many people for a successful warm room. Of those households we selected, four had one occupant, four had two occupants, and one (a control) had three occupants. Of the 14 occupants, 9 were 60 yr or older at the time of the initial audit, four were 70 yr or older and one was under 20 yr. All of the warm room houses were two stories, as were most of the controls. All had central gas systems, either forced air or gravity, and many had gas fireplaces, usually unused. The homeowners in the retrofit houses had all lived there from 25 yr to 45 yr. The owners of the control houses had lived there for 5-45 yr.

Table 1. Characteristics of experimental (warm room) houses and control houses

House ID	No. of Occu- pants	Occpt Ages ^a (yr)	Floor Area (ft ²)	Bldg Agea (yr)	Gas Use ^a (therm/yr)	Rooms and Floors (#/#)	Years in Home (yr)	Heatg System Type	Gas Fire- place Exist /Used	Ap- pliances (ex stove)	Air Condi- tion- ers
WK1 WK3 WK4 WK5 WK6†	1 2 2 2 2	86 83/70 60 69 84/65	1425 1512 ^c 1598 1675 ^d 1292 ^h	NA 69 NA 105 50	1717 1894 2106 1607 1365	7/2 9/2 ^c 9/2 7/2 ^d 7/2+	45 28 26 25 34	FA GA FA FA GA	Y/N Y/N Y/N Y/N Y/Y N/N	N dryer N dryer dryer	0 3W 0 0
CK4 CK5 CK6 CK8	1 1 3 1	57 68 66/? 39	1394 ^e 1418 3644 984	-70 77 NA NA	1335 ^f 1687 ^f 4346 ^f 1418	9/2 8/2+ 9/3 6/1	8 45 36 5	GA ^g FA FA,2GU GA	Y/N Y/Y Y/N Y/Y	dryer dryer 3 stoves dryer	0 3W 2W

WK2 dropped from program, replaced by WK6. Some control houses also dropped; see text.

Occupant and building ages are given as of the 1/83 audit.

Gas use is the average of 1981, 1982, and 1983/84 NAC unless otherwise stated

of rooms includes bathroom(s).

Heating system types are all central gas, except where noted and are further indicated as:

FA=gas central forced air GA=gas central gravity air GU=gas unit heater.

None of the homeowners reported use of auxiliary heaters (gas or electric) except occasional use of bathroom heaters.

Under "Air conditioner", "W" stands for window unit.

Excluding 3 unheated rooms, area = 1170 ft² Excluding unheated bedroom, area = 1548 ft²

Excluding unheated back room, area = 1333 ft².

Average of 1981 and 1983/84 NACs only. Replaced 1983/84.

Excluding unheated area, area = 1215 ft².

2.3 Instrumentation

The Kansas City Gas Company, at the city's request, provided submeters for the warm room houses. We provided wind-up thermographs to measure indoor temperatures (at least one per house, and two per warm room house when possible). The homeowners were responsible for making gas readings and changing the thermograph charts on a weekly basis. The gas readings were recorded on copies of gas company meter reading cards, which require marking the position of hands on meter dials; the actual numerical readings were made by LBL. The use of weekly intervals allows mistakes in reading to be fairly easily detected, and the few readings which cannot be corrected can be eliminated from the data set without a great loss of information (i.e. a loss of only a week, compared to a whole month with utility readings). In houses with both a total and a submeter, ambiguous readings can also often be resolved by comparing the two. In general the readings seemed reasonably accurate and most of the homeowners were very reliable in sending the data every week.

Blower door measurements were made at each of the retrofit houses before and after warm room installation. Indoor air was monitored for nitrogen dioxide, formaldehyde, and radon before and after retrofit in both the warm and cool zones.

2.4 Retrofit design and installation

The retrofits were planned by designers in Kansas City in consultation with the homeowners. All five houses have the warm rooms downstairs, where the occupants spend most of their time during the day. The four houses with two occupants had a total of three warm rooms each; the house with one occupant had two warm rooms. The kitchen was included in the warm zone in all houses. One occupant moved her bed downstairs for sleeping; the rest continued to sleep in the cool bedrooms upstairs. Zoning was accomplished by closing furnace dampers to the cool rooms and opening them fully to warm rooms. Curtains were provided in doorways as necessary to maintain the zoning. Warm air registers were opened in warm rooms and closed in cool rooms. The object was not to

provide complete zoning, since damage to water pipes and the building structure might result, but to maintain cool room temperatures down to about 50°F. In addition, ducts to the warm rooms were taped and insulated, warm room exterior walls were insulated (where possible), heat lamps were provided in the bathrooms, heat tape was applied to water pipes near exterior basement walls, and general weatherization was carried out in the warm rooms (caulking, weatherstripping, plastic storm windows). Throughout the installation residents were instructed in the management of the warm room.

In February 1986, a few months after the retrofits were completed, we conducted a survey to see how well the occupants were using their warm rooms and to ask them about how it had affected their lifestyles and comfort, and if they had any suggestions for improving future retrofits. A follow-up survey in March 1986 included questions about indoor air quality, a check of the instrumentation, and an evaluation of the performance of the retrofit.

3. RESULTS

3.1 Effectiveness of zoning

Table 2 shows the effect of zoning on indoor temperatures. The numbers are not strict averages of temperatures in the warm or cool zones; they were measured by a thermograph placed in one room of each zone and serve rather as indicators of average temperatures;

Table 2. Effect of zoning on indoor temperatures in warm room houses

House ID	Start	End	Warm		Cool		Warm-	Post-	Post-
	Date	Date	Room	Data	Room	Data	Cool Rm	Pre	Pre
			Temp.	Points	Temp.	Points	ΔT	Warm Rm	Cool Rm
	(Y-Mo-Dy)	(Y-Mo-Dy)	(°F)	(#)	(°F)	(#)	(°F)	ΔT(°F)	ΔT (°F)
WK1 Pre	84/10/01	85/05/31	75.1	18	76.3	19	-1.2		
WK1 Post	85/12/23	86/03/04	72.0	2	57.3	11	14.7	-3.1	-19.0
WK3 Pre	84/10/01	85/05/31	74.1	33	80.0	35	-5.9		
WK3 Post	86/02/03	86/03/24	69.9	8	69.3	8	.6	-4.2	-10.7
WK4 Pre	84/10/01	85/05/31	72.9	30	NA	_	_	_	
WK4 Post	85/12/26	86/03/22	73.8	12	59.3	8	14.5	+0.9	-
WK5 Pre	84/10/01	85/05/31	67.8	33	NA.	_	_		
WK5 Post	85/12/26	86/03/04	72.0	10	53.8	6	18.2	+4.2	-
WK6 Pre	84/10/01	85/05/31	72.2	33	NA	_			
WK6 Post	85/12/23	86/03/24	68.1	14	53.3	7	14.8	-4.1	

By April, 1986, temperatures in the cool room began to rise due to warmer outside weather. Each warm or cool temperature is the average temperature in one warm or cool room, respectively.

in some of the houses, only one thermograph was present before the retrofit. In Table 2, the average temperatures are through March, to indicate the effectiveness of zoning in cold weather. By April, temperatures in the cold rooms were already rising by about 10°F. After the retrofit we find temperature differences in the winter between warm and cool zones averaging about 12°F. In 3 of the houses, WK1, WK4, and WK6, the zoning seems to be working as intended, with cool room temperatures in the 50°F range. The occupants there are using the curtains consistently and the dampers appear to be working correctly. At WK1 and WK6 there were also 3 to 4°F reductions in the warm room temperatures, while WK4 showed a 1°F increase. In WK3, however, we found a difference of only 0.6°F between warm and cool rooms. Discussions with the homeowner and a check of temperatures in earlier years reveals an interesting situation—apparently the upstairs (nominal cool zone) had been badly overheated before the retrofit. Closing the dampers at the furnace served to reduce the temperature upstairs by about 11°F; coupled with a smaller reduction in downstairs temperature, the homeowners now find the entire house

much more comfortable. This and other observations of nominally unheated basements which were in fact warmed very well by uninsulated ducts and furnaces, suggests that more attention to duct insulation and balancing might be in order for conservation programs.

3.2 Energy savings and cost-effectiveness

Table 3 shows the gas savings for the warm room and control houses. Normalized annual consumption (NAC) was calculated for each house before and after the retrofit. The post-retrofit period was December 1985 through April 1986. Researchers at Princeton University have found that when using monthly meter readings, results from less than 10 consecutive readings may be unreliable, particularly if the readings fail to span warm and cold months. To test the reliability of our 5 month post-retrofit period based on weekly readings, we compared a pre-retrofit 5 month period with a full 12 month period and found that the differences in normalized annual consumption between the short and long periods were not significant, being substantially less than the error in measured savings. A similar check was performed on the control houses, with the same findings.

Table 3. Gas and electric savings in warm room and control houses

House ID	Warm room NAC ^a	Room NAC	Savings (th/yr)		10 %)	Error ^b (% of NAC)		Error ^b (% of heat)	Electricity Savings (kWhr/yr)	Electricity Savings ^d (th/yr)
WK1 WK3 WK4 WK5 WK6	2041 1897 1965 1075 1526	1124 1306 1398 1055 1218	917 592 567 21 308	231 169 169 117 149	45. 31. 29. 1.9 21.	11. 8.9 8.6 11. 9.8	49 38 33 NA NA	12. 10. 9.1 NA NA	-120 140 210 -220 -650	-12 14 22 -23 -67
CK4 CK5 CK6 CK8	1037 1663 4234 1450	965 1764 4038 1420	72 -101 196 30	182 149 537 240	7.0 -6.1 4.6 2.1	18. 9.0 13. 17.				

^aNormalized Annual Consumption (NAC) is total annual gas consumption normalized to long term average degree days to the best balance temperature found by regression (see text).

The results are very encouraging: in the three houses where the warm rooms were observed to be used effectively, the savings ranged from 21 to 47%, averaging 32%. This saving is the percentage savings in total gas usage; the percentage savings in gas for space heating alone is somewhat higher (see Table 3). At WK3, where zoning was not well maintained, but the overall house temperature was reduced, the savings were 31%. At WK5, the savings were 1.9% (smaller than statistical error in NAC calculation). Inspection and subsequent interviews with the residents at WK5 showed that several actions of the residents were counteracting the warm room strategy. The residents would typically leave the door from the kitchen (warm room) to the unheated basement open, saying 'it doesn't matter, because warm air rises and you wouldn't lose any heat.' They also would leave the hall door open that connected the two zones, and had opened the damper to one of the upstairs rooms. Overall, we measured average savings for the five houses to be 26%. Excluding WK5, the savings were 32%. Average savings for the control houses were 1.9%. We note that the sample is very small, and the controls only roughly matched to the warm room houses, but the fact that the warm room savings correlate with observed effectiveness of zoning, and the magnitude of the difference between savings for the warm room and

^bError calculated for 95% confidence interval, corresponding to roughly twice the standard error.

^cCalculated from regression of submetered fuel use versus degree days.

dSecond electricity savings column gives resource equivalent of savings in previous column. The factor of 0.10236 therm/kWhr includes electric power generation efficiency of 0.33. Resource equivalent gives rough price equivalent of gas versus electricity per unit of delivered heat.

control houses do indicate effectiveness of the retrofit. Our results compare favorably to results from weatherization programs nationwide, as cited by the General Accounting Office. Their estimated annual savings as a percent of total heating fuel (the same measure we used) ranged from 7.8% to 22.3%; the nationwide savings were 10.4%.

We also estimate changes in electricity consumption before and after the retrofit due to use of secondary space heaters (see Table 3). The estimated change in electricity consumption is scaled to annual use from billing data according to base 65°F days, after subtraction of base use. In the first four houses the increase or decrease is not large compared to the savings, but in WK6 there appears to be an increase on the order of 650 kWhr/yr—a significant fraction of the warm room savings. This is probably due to an electric heater the wife runs in one of the cool rooms to protect her plants. Whether the plants could actually tolerate 50°F temperature may affect the future savings in this and similar houses.

In the following economic analysis, retrofit costs include labor and materials only; as this was a research project, we did not estimate the costs of homeowner screening and educating that would need to be included in a demonstration project. Instead we outline some ways to minimize these expenses and maintain the cost-effectiveness of the retrofit.

The substantial attrition rate among households who originally applied for a warmroom retrofit was due to a variety of reasons, some not apparent until well into the retrofit process. A retrofit program devoted exclusively to installing warm rooms would therefore need to spend considerable resources on screening potential candidates. An alternative approach would be to include the warm room retrofit as an option in a conventional retrofit program. Auditors could be trained to identify potential candidates for warm room retrofits with little additional effort. This approach has already been adopted by the Institute for Human Development in Philadelphia. Some of the screening we did, such as checking for good correlations between gas use and variable-base degree days, would be unnecessary in an actual retrofit program. As discussed below (section 3.4) we found that the homeowner's motivation was critical to the success of the warm room. One approach to education that we believe helps to identify motivated homeowners, as well as reducing educating costs, is to require all prospective warm room recipients to attend a group workshop on the nature and use of the warm room. This tends to discourage those who are not truly interested, allows material to be covered with a group of homeowners all at once, (reducing, though not eliminating, the need for later one-to-one instruction), and allows all the homeowners to hear answers to questions they might not have thought to ask themselves. We found, however, that some of the elderly applicants needed assistance in arranging carpools or other transportation, but believe the benefits of this approach outweigh the extra effort involved. We also found a follow-up visit after the installation to be valuable to correct any equipment maladjustment, or to identify any problems related to the homeowner's use of the rooms.

The cost of the retrofits ranged from \$1295 at WK3 to \$1580 at WK5, averaging \$1425. Table 4 shows cost-effectiveness for the warm rooms as measured by simple payback, cost of conserved energy (CCE), and return on investment for several different scenarios. We use both the current Kansas City natural gas price of \$0.28/therm and the 1984 national average residential gas price of \$0.60/therm, since we believe the former to be an unrealistically low indicator of gas prices (see note to Table 4). Although the physical components of the retrofits should last 10 yr or more, the effectiveness of the warm room also depends on occupant behavior, and we know very little about the persistence of this aspect. Therefore, we calculate economic indicators using retrofit lifetimes of 5 and 10 yr. In calculating the cost of conserved energy we use a real discount rate of 7%.

At the low Kansas City price the simple payback time is 5 yr and greater. Using the national average price the simple payback time ranges from 2.4 to 4.6 yr for WK1-4; WK5, where negligible savings were observed, has a 125 yr payback, and WK6 has a 7.4 yr payback for the house without the extra heating for the plants and a 9.5 yr payback with the extra heating. The cost of conserved energy (an index of retrofit cost which is used for comparison with current or expected energy prices—see note to Table 4) shows a strong relationship with retrofit lifetime: the results for a 10-yr life of a retrofit compare

Table 4. Cost-effectiveness of warm room retrofits

House ID	Savings (th/yr)	Warm Room Cost	Simple Payback ^a @.28\$/th (yr)	Simple Payback ^a @.6\$/th (yr)	CCE ^b 5 yr (\$/th)	CCE ^b 10 yr (\$/th)	ROI ^c @ 0.28 \$/th (%/yr)	ROI ^c @ 0.6 \$/th (%/yr)
WK1 WK3 WK4 WK5 WK6 WK6	917 592 567 21 308 241	1323 1295 1552 1580 1373	5.2 7.8 9.8 269. 16. 20.	2.4 3.6 4.6 125. 7.4 9.5	0.35 0.53 0.67 18. 1.1 1.4	0.21 0.31 0.39 11. 0.63 0.81	19 13 10 0.4 6 5	42 27 22 1 13

^aSimple Payback Time (SPT) is the number of years required for accumulated energy savings to equal retrofit cost, ignoring factors such as discount and inflation rates.

SPT = (retrofit cost)/(savings per year)

The first SPT is based on the current price of natural gas in Kansas City of \$0.28/therm (which had been \$0.42/therm a year previously). The second is based on the 1983 national average residential price of \$0.60/therm. We note that the average real (uninflated) price of residential natural gas has risen 5% per year in the last fifteen years (roughly doubling in that time), so that the current low price of Kansas City gas is not a reliable benchmark (Energy Information Administration, Annual Energy Review 1984, Washington, D.C., 1985).

^bCost of Conserved Energy (CCE), which is the cost (in dollars) divided by the levelized savings (in therms). It can be compared directly to the cost of energy which would otherwise have to be purchased: If the CCE of the retrofit is lower than the relevant energy price, the retrofit is economical. The CCE takes into account the discount rate and retrofit lifetime, but is unaffected by fuel inflation rate.

CCE = [i/(1- (1+i)⁻ⁿ)] x cost (\$)/savings (therms)
Where i = discount rate (taken here as 7% real (above inflation))
n = retrofit lifetime (here 5 or 10 years as indicated)

^CReturn On Investment (ROI) is the percentage return in energy savings (measured in dollars) for every dollar invested in the retrofit. It is used to compare the value of investing in conservation compared to alternative investments (e.g., savings account, mutual fund): the higher the ROI, the better the investment.

ROI = annual savings/retrofit cost

A levelized ROI, taking into account discount rate, fuel price escalation, and retrofit lifetime can be calculated, but for a real discount rate of 7%, lifetime of 5-10 years, and 5% real fuel escalation rate (15 year historical average) the results differ by at most about 10% (4 percentage points).

dAt WK6 an increase in electric heat for a plant room offset gas savings. Net savings are estimated by subtracting the resource equivalent (rough price equivalent) of the increase in electric use from gas savings.

considerably better to the average national residential gas price than those for a 5-yr life. For the latter, three houses are near or below the \$0.60/therm benchmark; for the former, all but WK5 lie near or below, with WK1 at \$0.21/therm.

Return on investment (ROI) is another commonly used investment decision tool. At the national benchmark price for natural gas, the four houses with significant savings show an ROI ranging from 11 to 42%, averaging 26%—better than most investment opportunities available to typical homeowners. Even at current low Kansas City gas prices, the four houses show an average ROI of 12%.

3.3 Indoor air quality

We measured nitrogen dioxide (NO₂), formaldehyde (HCHO), and radon (Rn) inside and outside the living space, and base gas use (total minus furnace) during the NO₂/HCHO monitoring period. All air quality measurements were made using passive samplers. Each house had 10 samplers for formaldehyde and nitrogen dioxide and two samplers for radon. In addition to the air quality measurements, blower door tests were made on the house to measure their air tightness. The blower door tests showed a post-retrofit reduction in leakage area of about 1–36% for four houses, with WK6 showing an apparent increase of 22%.

The pre-retrofit NO₂ measurements showed several houses with NO₂ levels in the kitchen slightly above the EPA-recommended maximum level of 50 ppb (see Table 5). One living room was also slightly above the maximum and another was well above (95.9 ppb).

Table 5. Levels of nitrogen dioxide (pre- and post-retrofit) in warm room houses

House ID	Warm Room Pre (ppb)	Warm Room Post (ppb)	Change in w.r. (ppb)	Cool Room Pre (ppb)	Cool Room Post (ppb)	Change in c.r. (ppb)	Outside Pre (ppb)	Outside Post (ppb)	Change Outside (ppb)
WK1 WK3 WK4 WK5 WK6	45.6 56.6 44.1 95.9 NA	41.7 37.7 33.3 138.3 57.0	-3.9 -18.9 -10.8 42.4	28.0 41.0 28.6 NA NA	24.7 27.3 16.7 95.3 53.0	-3.3 -13.7 -11.9 -	17.9 19.8 15.6 18.8 NA	17.3 18.0 16.7 17.3 17.7	-0.6 -1.8 1.1 -1.5

^aOriginal WK2 replaced by WK6 before retrofit but after initial round of air quality measurements (see text); therefore no pre-retrofit measurements available for WK6.

^cBecause of gas fireplace and gas stove use, initial measurements were made in the kitchen and living room (both part of warm room area). No pre-retrofit measurements of cool area available.

The latter was in WK5, where the homeowners had been using a poorly vented gas fireplace, as well as their gas oven, for heating. We therefore had some concerns about air quality after the warm room installation, since all warm areas included the kitchen and all had gas stoves. In the post-retrofit monitoring, however, we found that three houses were below the maximum in both warm and cool zones, and one was slightly above (WK6, at 57.0 ppb in the warm room and 53.0 ppb in the cool room. The 50 ppb maximum is an annual average, and it is likely that levels are lower in the summer when the house is opened up, so the slightly elevated levels are probably not a serious concern). But at WK5, where the owners had not understood the warm room concept, the levels were even higher than before the retrofit (138.3 ppb in the warm room, 95.3 ppb in the cool room), despite the fact that they said (and submetered vs total gas use records confirmed) that they no longer used the gas fireplace and oven for heating. The puzzle was solved during one of the household visits, when the interviewers established that not only was the gas-dryer flue disconnected, but the common furnace/water heater flue did not, as appeared to a casual glance, connect to the chimney. That the levels in the other houses showed reductions after the retrofit appears to be due, at least in part, to decreased stove/oven use for space heating. In each of the three houses showing a reduction in NO₂, there was also a drop in base gas use (total minus submetered). At WK4 the resident said that she had used her oven "a lot" for space heating before the retrofit, but has since only used the stove "once or twice" for that purpose. At WK6 the wife also had used the oven "a little" for space heating before the retrofit, but does not now. House WK6, where the post-retrofit NO₂ levels were slightly above the EPA maximum, also had the highest post-retrofit base gas use (8 therm/week, compared to the average 5.8 therm/week). Because it had been a backup house during the pre-retrofit monitoring, no initial NO₂ data are available. There was no strong correlation between changes in NO₂ levels and changes in infiltration rate.

None of the houses had formaldehyde levels above the strictest current guideline of 100 ppb (see Table 6). Changes in the warm-room levels ranged from -57% to +7.3%. The changes were not strongly correlated with changes in outdoor levels, stove use, or infiltration rates. The only house where new furniture had been acquired (a potential source of formaldehyde) was WK3 where there was a slight increase in formaldehyde.

The radon levels in the basements were, on average, almost three times as high as those measured three years before, ranging from 1.37 to 5.35 picoCuries per liter (pCi/l) compared to 0.82 to 2.42 pCi/l (see Table 7). The radon levels in the warm rooms also increased after the retrofit, though the percentage increase was less, with post-retrofit measurements ranging from 1.37 to 3.04 pCi/l, and pre-retrofit measurements ranging from 0.75 to 2.91 pCi/l. The proposed Environmental Protection Agency Standard for radon is 4.0 pCi/l.

Table 6. Levels of formaldehyde (pre- and post-retrofit) in warm room houses

House ID	Warm Room Pre (ppb)	Warm Room Post (ppb)	Change in w.r. (ppb)	Cool Room Pre (ppb)	Cool Room Post (ppb)	Change in c.r.	Outside Pre (ppb)	Outside Post (ppb)	Change Outside (ppb)
WK1 WK3 WK4 WK5 WK6 ^a	29.4 35.7 56.4 36.2 NA	27.7 38.3 24.3 33.3 30.7	-1.7 2.6 -32.1 -2.9	26.0 61.7 28.0 - NA	18.2 41.7 12.7 37.7 33.0	-7.8 -20.0 -15.3 -	26.0 15.7 12.7 26.5 NA	14.3 18.3 8.3 24.0 18.7	-11.7 2.6 -4.4 -2.5

^aOriginal WK2 replaced by WK6 before retrofit but after initial round of air quality measurements (see text); therefore no pre-retrofit measurements available for WK6.

^bBecause of gas fireplace and gas stove use, initial measurements were made in the kitchen and living room (both part of warm room area). No pre-retrofit measurements of cool area available.

which is higher than any of the radon levels we measured in the living areas of these houses. In four of the houses, in fact, the ratio of radon in the living space to radon in the basement was lower after the retrofit, that is, a smaller proportion of the radon from the basement was getting into the living space after the retrofit. At WK5, where the basement door to the kitchen (warm room) was left open, the basement did not show as high an increase in radon as the other houses, and the level in the warm room was the same as in the basement. These observations support the suspicion, mentioned earlier, that considerable mixing of basement and warm room air is occurring (the smaller increase in the basement could be due in part to radon escaping upstairs until warm room and basement levels were equal).

Table 7. Levels of radon (pre- and post-retrofit) in warm room houses

-							Houses	
House ID	Basement Radon	Basement Error	Living Room Radon	Living Room Error	Post- Pre Retrofit	Post- Pre Retrofit	Post- Pre Retrofit	Post- Pre Retrofit
	(pCi/l)	(SD%)	(pCi/l)	(SD%)	Basemt (pCi/l)	Basemt (%)	Lvg rm (pCi/l)	Lvg rm (%)
WK1 pre WK1 post	2.42 4.12	10.2 14.8	1.92 2.98	11.5 17.6	1.70	70	1.06	55
WK3 pre WK3 post	1.47 4.92	13.1 13.6	2.91 2.62	9.3 18.7	3.45	235	-0.29	-10
WK4 pre WK4 post	0.82 5.35	17.7 12.8	0.75 3.04	18.5 17.0	4.53	552	2.29	305
WK5 pre WK5 post	1.17 1.37	14.7 25.4	1.02 1.37	15.8 25.4	0.20	17	0.35	34
WK6 post	4.21	14.7	2.45	19.4	NA	NA	NA	N

To summarize the findings on indoor air quality, we found acceptable levels of NO₂ in four of the five test houses. In some cases, the levels had decreased after the retrofit, probably due to the decreased use of the unvented gas stoves for space heating. In WK5, where levels were two to three times the EPA outdoor standard, the problem appeared to stem from the installation of a new gas furnace and water heater that was improperly vented, rather than from the warm room retrofit. None of the houses had formaldehyde levels above the strictest current guideline. While on average, radon levels increased, the levels in all houses were below both the proposed EPA standard and the current Swedish

bUsing measurement without outlier for WK3.

standard for existing houses. In three houses, the ratio of radon in the living space to radon in the basement was lower after the retrofit, the exception being WK5, where the basement door was routinely left open.

3.4 Comfort, lifestyle and occupant perception of warm rooms

In post-retrofit interviews, residents were asked whether the warm room had changed their lifestyles and level of comfort, and whether their reactions were positive or negative. In the four houses where the occupants used the warm rooms correctly and where significant energy savings were measured, the residents were very positive in their reactions to the warm room. They mentioned both their lower heating bills and the increased comfort resulting from the retrofit. At WK5, where problems were observed with the use of the retrofit, the residents were fairly critical. In three of the houses residents liked having the use of the downstairs instead of being forced by cold weather to go upstairs, where it was warmer (before the retrofit). Having cold bedrooms did not seem to be a problem, though in a few cases, owners resorted to some use of an electric heater. On the lifestyle changes, one resident observed that her activities had changed as a result of the retrofit, but that she accepted that as "there are things you do normally that you don't do other seasons." At WK3, where the zoning did not work as well as intended, but the overheating of the upstairs was reduced, the couple spend their time downstairs (in the nominal warm room) but like having the temperature comfortable upstairs. At WK1, the homeowner said that she had enough room in the warm zone, but if she could, she would heat the living room as well. At WK3 the residents also said they had enough room in the warm space. At WK5, the homeowners felt they had too little room, and would have preferred having a downstairs bedroom included instead of the kitchen. At WK6 the couple said they had enough room; when grandchildren visited over the holidays, they "let a little warmth go upstairs we had no problems."

There were several comments that the heat lamps installed in the bathrooms were inadequate for keeping warm before or after bathing. Some condensation had been noticed during the coldest weather on cool room windows, but none of the owners seemed to think there was a serious problem. With the exception of WK5, the owners liked the retrofit and offered no major suggestions for changes. It is worth noting that in a survey of warm rooms installed by the Institute for Human Development (IHD) in Philadelphia, which also pre-screens applicants and counsels them in the use of the warm room, 28% of homeowners did not adapt to or use their warm room and an additional 11% showed poor adaptation. In both cities it appears that improved screening and/or counselling might improve overall program savings.

4. CONCLUSIONS

We found substantial energy savings in houses where homeowners understood the use of the warm room retrofit and used it correctly. In one case the savings appear to be due more to a reduction in overheating than to zoning. Even considering the house where the warm room was not used well, overall savings were about 26%, over twice the average savings of 10% for weatherization programs of comparable cost reported by a recent GAO report on national weatherization programs. The warm room did not appear to create or significantly aggravate problems with indoor air quality. Occupant reaction was positive, with four of the households adapting well to the warm room. These results suggest that a larger warm room project, with measurements of energy savings and indoor air quality is well worth pursuing.

We suggest that several areas in particular are worth investigating: (i) Improvements in screening and/or counseling the potential recipients to increase the proportion of homeowners who adapt well to the warm room. (ii) Reduced cost of retrofit materials, particularly the curtains, which in this project ran from \$113 to \$338. Care must be taken, however, not to resort to materials so cheap that they become unattractive to the homeowners. (iii) Measuring the persistence of savings over several years. (iv) Attention

given to the ducts—currently the forgotten link between envelope and furnace. Judging from the overheated (nominally unheated) basements we observed, as well as problems in duct balancing, there may be significant savings to be realized from sealing, insulating, and adjusting the distribution system. (v) The influence of climate on warm room effectiveness. Since the warm room savings can be viewed as primarily due to a lowering of the balance point (resulting in a shorter heating season), the distribution of outdoor temperatures may have a large effect on savings. That is, the retrofit may be most effective in areas such as the Pacific Northwest, where there are long portions of the heating season near or above the post-retrofit balance temperature.

Acknowledgements—This work was supported by the Assistant Secretary for Conservation and Renewable Energy, Office of Building and Community Systems, Building Systems Division of the U.S. Department of Energy under Contract No. DE-AC03-76SF00098. We would also like to acknowledge the time and effort of B. Kjelshus, City of Kansas City, R. Simms of Westside Housing, Kansas City, J. Harrison, LBL, for analyzing the air quality measurements, C. Goldman, LBL and G. Dutt, Princeton University (for their helpful review comments), the Kansas City Warm Room Advisory Committee, and the participation and cooperation of the homeowners themselves.

REFERENCES

- B. S. Wagner, Economic Design Criteria for Warm Rooms Retrofits, LBL Report, BED-WP-83-01, Lawrence Berkeley Laboratory, Berkeley, Calif. (1983).
- J. Allegretti, Warm Room Report, Institute of Human Development, 718 W. Norris St, Philadelphia, PA 19122 (1984).
- 3. L. R. McFarland, Energy Auditor Retrofitter, 3(2), 29 (1986).
- C. N. Grandy, Case History of Residential Comfort Zone, Union Electric Company, PO Box 149, St. Louis, MO 63166 (1983).
- 5. M. F. Fels and M. Goldberg, Energy 7, 489 (1982).
- 6. J. Rachlin, M. F. Fels and R. H. Socolow, Energy Buildings 9, 149 (1986).
- 7. U.S. Government, General Accounting Office, 'Low-income weatherization Better Way of Meeting Needs in View of Limited Funds, GAO-RCEE-86-19, Government Printing Office, Washington, D.C. (1985).
- 8. U.S. Government, National Security Act of 1980 for U.S. Government Conservation and Solar Investments, Government Printing Office, Washington, D.C. (1981).
- 9. J. Allegretti, op. cit.